



RMP ENGINEERING SERVICES

Address: #391 Brgy. Rizal, San Leonardo, Nueva Ecija, 3102
Email: Pangilinan.ronmarb@gmail.com | Contact: +63960-244-6185

BILL OF QUANTITY

PROPOSED TWO STOREY RESIDENTIAL HOUSE WITH BASEMENT



Perspective View of the Proposed Two-Storey Residential House w/ Basement

PROJECT LOCATION:	_____
OWNER:	_____
PROJECT CODE:	RMP-2026-004
TOTAL FLOOR AREA:	234.36 SQ.M
ITEM SUMMARY:	General Requirements Equipment Rental Siteworks Civil / Structural Works Masonry Works Steel Works Roofing Works Painting Works Tile Works Ceiling Works Doors Glass / Windows Electrical Works Plumbing Works

PREPARED BY:

ENGR. RON MAR B. PANGILINAN, RCE

PRC NO. : _____
VALIDITY : _____
PTR NO. : _____
ISSUED ON : _____
ISSUED AT : _____
TIN NO. : _____



RMP ENGINEERING SERVICES

Address: #391 Bgry. Rizal, San Leonardo, Nueva Ecija, 3102
Email: Pangilinan.ronmarb@gmail.com, Contact: +63960-244-6185

Project: PROPOSED TWO STOREY RESIDENTIAL HOUSE W/ BASEMENT

Location:

Client/Owner:

Total Floor Area: 234.36 sqm

Cost/sqm: ₱45,046.22 per sqm

BILL OF QUANTITY

GENERAL REQUIREMENTS	QUANTITY	UNITS		COST/ITEM
Mobilization	1	ls		15,000.00
Temporary Facilities				5,000.00
Signed and Sealed Building Plans	1	ls		
Water Consumption/Connection	1	ls	Shouldered by Owner	-
Electric Consumption/Connection	1	ls	Shouldered by Owner	-
Sub-Total				20,000.00

EQUIPMENT RENTAL	QUANTITY	UNITS		COST/ITEM
Welding Machine/Grinder/Drill	1	ls		15,000.00
One Bagger Mixer	1	ls		35,000.00
Sub-Total				50,000.00

SITE WORKS	QUANTITY	UNITS		COST/ITEM
Excavation/Embankment	1	ls		151,469.20
Sub-Total				151,469.20

STRUCTURAL WORKS	QUANTITY	UNITS		COST/ITEM
Wall Footing	1.16	cu.m.		11,428.20
Retaining Walls	40.64	cu.m.		1,080,588.60
Column Footing	20.37	cu.m.		229,597.20
Tie Beams	7.46	cu.m.		203,382.90
Columns	20.16	cu.m.		772,778.48
Slab on Grade	7.67	cu.m.		72,588.60
Concrete Canopys	2.84	cu.m.		26,720.74
Second Floor Beams	11.03	cu.m.		285,534.90
Third Floor Beams	9.24	cu.m.		248,994.90
Second Floor Slab	10.08	cu.m.		233,654.40
Third Floor Slab	9.56	cu.m.		228,438.00
Roof Beams	4.41	cu.m.		120,575.70
Material Cost	144.59	cu.m.		3,514,282.62
Labor Cost				1,405,713.05
Sub-Total (Labor Cost + Material Cost)				4,919,995.67

MASONRY WORKS	QUANTITY	UNITS		COST/ITEM
CHB including reinforcements and Plastering	404.114	sqm		519,858.27
Material Cost				519,858.27
Labor Cost				207,943.31
Sub-Total (Labor Cost + Material Cost)				727,801.58

STEEL WORKS	QUANTITY	UNITS	COST/ITEM
Trusses	1	ls	64,962.07
Purlins	1	ls	33,489.16
Balcony Railings	1	ls	-
Steel Gate	1	ls	-
Canopy Support/Trellis	1	ls	44,152.92

Material Cost 142,604.15

Labor Cost 57,041.66

Sub-Total (Labor Cost + Material Cost) 199,645.82

THERMAL & MOISTURE PROTECTION (ROOFING WORKS)	QUANTITY	UNITS	COST/ITEM
Rib Type Long Span Roof 0.40mm Thick	113.8	ln.m.	114,886.11
Polycarbonate Roofings - Twin Wall	9.45	ln.m.	20,838.96

Material Cost 135,725.07

Labor Cost 54,290.03

Sub-Total (Labor Cost + Material Cost) 190,015.10

Painting Works	QUANTITY	UNITS	COST/ITEM
Masonry	404.114	sqm	174,440.70
Steel	164.2	sqm	13,104.00

Material Cost 187,544.70

Labor Cost 75,017.88

Sub-Total (Labor Cost + Material Cost) 262,562.58

Tile Works	QUANTITY	UNITS	COST/ITEM
Tileworks at Ground Floor	66	sqm	92,521.80
Tilesworks Second Floor	96	sqm	134,309.70
Tilesworks Third Floor	90.82	sqm	126,875.70
Tiles at Bathroom	76.345	sqm	109,626.78
Tile Cladding/Stone Cladding	19.475	sqm	54,597.25
Fluted Wall Panels Outdoors	21.4484	sqm	54,444.60

Material Cost 572,375.84

Labor Cost 228,950.34

Sub-Total (Labor Cost + Material Cost) 801,326.17

Ceiling Works	QUANTITY	UNITS	COST/ITEM
Interior Ceilings	274.3675	sqm	155,798.24
Fluted Wood Ceilings	9.78	sqm	27,370.22
PVC Ceilings	28.7	sqm	77,006.16

Material Cost 260,174.63

Labor Cost 104,069.85

Sub-Total (Labor Cost + Material Cost) 364,244.48

Doors	QUANTITY	UNITS	COST/ITEM
Wooden Doors	24.725	sqm	155,490.30
Glass Doors	30.701	sqm	177,893.10

Material Cost 333,383.40

Labor Cost 133,353.36

Sub-Total (Labor Cost + Material Cost) 466,736.76

Glass/Windows	QUANTITY	UNITS	COST/ITEM
Sliding Glass Windows and Awning	37.46	sqm	256,825.80
Glass Railing on Aluminum Framings	6	sqm	60,480.00

Material Cost 317,305.80

Labor Cost 126,922.32

Sub-Total (Labor Cost + Material Cost) 444,228.12

Electrical Works	QUANTITY	UNITS	COST/ITEM
Roughing Ins, Wires, Cables and Panel Boards	1	ls	48,284.40
Electrical Devices and Lighting Fixtures	1	ls	106,703.10
Material Cost			154,987.50
Labor Cost			61,995.00
Sub-Total (Labor Cost + Material Cost)			216,982.50

Plumbing Works	QUANTITY	UNITS	COST/ITEM
Roughing Ins, Waterlines and Wastelines	1	ls	170,906.83
Septic Tank	1	ls	32,565.49
Catch Basin	1	ls	12,494.48
Canal	1	ls	-
Plumbing Fixtures	1	ls	220,399.20
Material Cost			436,365.99
Labor Cost			174,546.40
Sub-Total (Labor Cost + Material Cost)			610,912.39

Total Direct Cost		9,425,921.00
Transportation & Miscellaneous	3.50%	329,907.24
Project Supervision (Overhead Cost)	3.50%	329,907.24
Profit Margin	5.00%	471,296.05

Total Project Cost	10,557,032.00
---------------------------	----------------------

TOTAL AMOUNT IN WORDS
TEN MILLION FIVE HUNDRED FIFTY-SEVEN THOUSAND THIRTY-TWO PESOS ONLY.

Excluded Items

- 1 Taxes and Insurances
- 2 Furnitures, Appliances, Bookshelves, modular counter top and kitchen overhea
- 3 Aircondition units ands Equipments
- 4 Landscaping
- 5 Main wire from secondary to Entrance Cap
- 6 Chandeliers
- 7 Materials for Plumbing Fixtures (Lavatory, Sink, Toilet, Faucet, Floor Drain, Shower, etc)
- 8 Fire Exit Stairs
- 9 Cladding Works and Finishing Materials (Stone Tiles, Flutter Wood, PVC Stucco Finish)
- 10 Window and Glass doors
- 11 Glass Railings and Steel Railings
- 12 Stair Railings
- 13 Spiral Stairs
- 14 Water Tanks

PREPARED BY:

ENGR. RON MAR B. PANGILIINAN, RCE

RMP Engineering Services

APPROVED/ACKNOWLEDGE BY:

NAME

OWNER