

PROFESSIONAL PORTFOLIO



01 PROFESSIONAL PROFILE

02 SOFTWARE & TECHNICAL SKILLS

03 ESTIMATING WORKFLOW

04 SAMPLE ESTIMATING PROJECTS

05 CONSTRUCTION & QA/QC EXPERIENCE

06 CERTIFICATIONS & TRAINING



**BUILT ON PRECISION.
DRIVEN BY QUALITY.**

ENGR. RON MAR B. PANGILINAN

QA/QC CIVIL ENGINEER | PLANNING ENGINEER | CONSTRUCTION ESTIMATOR | QUANTITY TAKEOFF SPECIALIST



EMAIL: Pangilinan.ronmarb@gmail.com



LinkedIn: [linkedin.com/in/engr-ron-mar-pangilinan/](https://www.linkedin.com/in/engr-ron-mar-pangilinan/)
Portfolio: <https://engr-ron-mar-pangilinan.github.io/>



CONTACT NO.:

+63960-244-6185 / +63967-084-0495



ADDRESS:

San Leonardo, Nueva Ecija, Philippines 3102





PROFILE SUMMARY:

Registered Civil Engineer and Construction Estimator with hands-on experience in **quantity takeoff, cost estimating, structural/civil engineering, and QA/QC**. Skilled in interpreting architectural, structural, civil, and MEP drawings and developing detailed quantity takeoffs, **BOQ/BOM**, and cost estimates.

Experienced in construction planning, project coordination, quality control, and technical documentation within a multinational solar power project. Proficient in **PlanSwift, Bluebeam Revu, Microsoft Excel, AutoCAD, and Primavera P6**.

Focused on delivering accurate quantities, practical solutions, quality workmanship, and well-organized construction documentation—from planning and design through execution.

CORE STRENGTHS

QUANTITY TAKEOFF • COST ESTIMATING • BOQ/BOM • QA/QC • DRAWING INTERPRETATION
CONSTRUCTION PLANNING • PROJECT COORDINATION • TECHNICAL DOCUMENTATION

SOFTWARE & TECHNICAL SKILLS 02

PLANSWIFT 11

Materials & Labor Quantity Takeoff | Cost Estimating Reports | Custom Assemblies & Automated Takeoff | Structural Concrete & Rebar | Architectural Works | Roofing Works | Multi-trade Estimating



BLUEBEAM REVU 21


Material & Labor Quantity Takeoff | PDF Measurement & Markups | Construction Document Review | Architectural, Concrete & MEP Estimating

ENGINEERING & DESIGN SOFTWARE



REMOTE WORK & COLLABORATION TOOLS





04 SAMPLE ESTIMATING PROJECTS

1. PROPOSED TWO-STOREY RESIDENCE – 178.70 sq.M (1,923 sq.FT.)

Estimated Construction Cost: USD 96,586.10

Item Summary:

General Requirements

Siteworks

Civil / Structural Works

Architectural Works

Plumbing Works

Electrical Works

Tinsmithry / Roofing Works

Metal Works

Cabinetry and other Finishing Works



Note: Drawings and project information are presented for training and professional portfolio purposes. Actual project records and confidential information are not reproduced.

SAMPLE BILL OF MATERIALS

BILL OF MATERIALS					
Item No.	Item Description	Quantity	Unit	Unit Price, Php	Amount, Php
III. CIVIL/STRUCTURAL WORKS					
III.i. CONCRETING/MASONRY WORKS/REINFORCEMENTS					
	RC Footings (3000 PSI)	6.77	cu.m		
	• Cement	51.00	bgs	250.00	12,750.00
	• Sand	4.00	cu.m	1,000.00	4,000.00
	• Gravel 3/4"	7.00	cu.m	1,450.00	10,150.00
	• 16 mm def bar (6 meters)	48.00	pcs	480.00	23,040.00
	• 10 mm def bar (6 meters)	8.00	pcs	230.00	1,840.00
	• GI Tie Wire # 16	5.00	kgs	85.00	425.00
	RC Columns (3000 PSI)	9.43	cu.m		
	• Cement	71.00	bgs	250.00	17,750.00
	• Sand	5.00	cu.m	1,000.00	5,000.00
	• Gravel 3/4"	10.00	cu.m	1,450.00	14,500.00
	• 16 mm def bar (6 meters)	140.00	pcs	480.00	67,200.00
	• 10 mm def bar (6 meters)	139.00	pcs	230.00	31,970.00
	• GI Tie Wire # 16	19.00	kgs	85.00	1,615.00
	Tie Beams (3000 PSI)	3.49	cu.m		
	• Cement	27.00	bgs	250.00	6,750.00
	• Sand	2.00	cu.m	1,000.00	2,000.00
	• Gravel 3/4"	4.00	cu.m	1,450.00	5,800.00
	• 12 mm def bar (6 meters)	57.00	pcs	290.00	16,530.00
	• 10 mm def bar (6 meters)	49.00	pcs	230.00	11,270.00
	• GI Tie Wire # 16	5.00	kgs	85.00	425.00
	Slab on Grade (3000 PSI)	11.63	cu.m		
	• Cement	88.00	bgs	250.00	22,000.00
	• Sand	6.00	cu.m	1,000.00	6,000.00
	• Gravel 3/4"	12.00	cu.m	1,450.00	17,400.00
	• 10 mm def bar (6 meters)	127.00	pcs	230.00	29,210.00
	• GI Tie Wire # 16	5.00	kgs	85.00	425.00
	Masonry Works	245.16	sq.m		
	• Concrete hollow block - 4"	944.00	pcs	15.00	14,160.00
	• Concrete hollow block - 6"	2428.00	pcs	18.00	43,704.00
	• Cement	227.00	bgs	250.00	56,750.00
	• Sand	19.00	cu.m	1,000.00	19,000.00
	• 10 mm def bar (6 meters)	189.00	pcs	230.00	43,470.00
	• GI Tie Wire # 16	7.00	kgs	85.00	595.00
III.ii. FORMWORKS					
	• Phenolic Board (4 x 8 x 1/2)	81.00	pcs	700.00	56,700.00
	• CWN Assorted Nail	117.00	kgs	80.00	9,360.00
	• Lumber for formworks (2" x 3" and 2" x 2")	5197.00	bd.ft	60.00	311,820.00
	• Standard H-Frame Set (1.2 x 1.7)	4.00	set	450.00	3,600.00
	• Platforms/Catwalk	8.00	pcs	350.00	5,600.00
	• Consumables/miscellaneous	1.00	lot	5%	19,354.00

BILL OF MATERIALS					
Item No.	Item Description	Quantity	Unit	Unit Price, Php	Amount, Php
IV. ARCHITECTURAL WORKS					
IV.i. CEILING WORKS					
	• Metal Furring (JEAMaxx G.24)	202.35	sqm		
	• Carrying Channel (JEAMaxx G.24)	63.00	pcs	130.00	8,190.00
	• Double U-Clip (JEAMaxx)	59.00	pcs	140.00	8,260.00
	• Wall Angle (JEAMaxx G.24)	391.00	pcs	5.00	1,955.00
	• Blind rivets 1/8" dia. X 1/2" (1000 PCS PER BOX)	148.00	pcs	80.00	11,840.00
	• Gypsum Board (9mm)	4.00	boxes	450.00	1,800.00
	• Gypsum Mesh Tape	53.00	pcs	750.00	39,750.00
	• Metal Spandrel (0.15 x 0.8)	6.00	pcs	120.00	720.00
	• black screw	603.00	pcs	75.00	45,225.00
	• Consumables/miscellaneous	1866.00	pcs	1.00	1,866.00
		1.00	lot	10%	11,960.60
				Sub Total =	131,566.60
				Labor Cost =	52,626.64
IV.ii. DOORS & GLASSES					
	GLASSES	43.47	sqm		
	• GLASS ENCLOSURE	2.00	set	15,000.00	30,000.00
	• Sliding Door (2-panel 1.6 x 2.1 with 1/4" Bronze glass & analok finish)	2.00	set	20,000.00	40,000.00
	• Fixed Window With 1/4" Glass (1.2 x 2.1)	1.00	set	12,000.00	12,000.00
	• Awning Windows & Fixed (0.6 x 0.6)	2.00	set	3,000.00	6,000.00
	• Exterior Windows (1.0 x 1.2)	7.00	set	5,000.00	35,000.00
	• Exterior Windows (1.0 x 1.0)	3.00	set	5,000.00	15,000.00
	• Fixed Window With Glass (0.6 x 5.4)	3.00	set	18,000.00	54,000.00
	DOORS				
	• Matwood Solid Panel Doors (1.2 x 2.1) WITH ACCESSORIES	1.00	set	20,000.00	20,000.00
	• Matwood Panel Type Doors (0.8 x 2.1)	3.00	set	18,000.00	54,000.00
	• Matwood Panel Type Doors (0.7 x 2.1)	1.00	set	15,000.00	15,000.00
	• CR Door - Painted Flush Door (0.8 x 2.1)	2.00	set	10,000.00	20,000.00
				Sub Total =	301,000.00
				Labor Cost =	120,400.00
IV.iii. TILE WORKS (Supply and installation of wall and floor tiles)					
	• Porcelain (0.60x0.60)	175.14	sqm		
	• Anti-Slip Ceramic (0.40x0.40)	145.00	pcs	350.00	50,750.00
	• Anti-Slip Ceramic (0.30x0.30)	130.00	pcs	70.00	9,100.00
	• Porcelain (0.20x0.60)	62.00	pcs	40.00	2,480.00
	• Marble Tile (0.30x0.30)	145.00	pcs	200.00	29,000.00
	• Wood-look Tile (0.15x0.60)	36.00	pcs	100.00	3,600.00
	• Wood-look Tile (0.20x1.0)	414.00	pcs	120.00	49,680.00
	• Herringbone Brick (0.20x0.10)	252.00	pcs	170.00	42,840.00
	• Tile Adhesive	481.00	pcs	40.00	19,240.00
	• Tile Adhesive (Heavy Duty)	16.00	bags	350.00	5,600.00
	• Cement	6.00	bags	530.00	3,180.00
	• Sand	56.00	bgs	250.00	14,000.00
	• Tile Grout (2kg)	5.00	cu.m	1,000.00	5,000.00
	• tile spacers	46.00	bags	113.00	5,198.00
	• Consumables/miscellaneous	4736.00	pcs	2.00	9,472.00
		1.00	lot	5%	12,457.00
				Sub Total =	261,597.00
				Labor Cost =	104,638.80

Note: Drawings and project information are presented for training and professional portfolio purposes. Actual project records and confidential information are not reproduced.

04 SAMPLE ESTIMATING PROJECTS

3. PROPOSED TWO-STOREY RESIDENTIAL BUILDING – 198.04 sq.M. (2,132 sq.FT.)

Estimated Construction Cost: USD 51,702.03
Item Summary: Siteworks / Concrete Works
Reinforcement Works / Formworks
Ceiling Works / Tile Works



RMP ENGINEERING SERVICES

Address: #391 Bgry. Rizal, San Leonardo, Nueva Ecija, 3102
Email: Pangilinan.ronmarb@gmail.com, Contact: +63960-244-6185


CONSTRUCTION QUANTITY TAKE-OFF

Name	Description	Qty	Units
SITWORKS			
TOTAL EXCAVATION		38	CU M
TOTAL GRAVEL BEDDING		9.7	CU M
TOTAL BACKFILLING		72.82	CU M
CONCRETING			
Lean Concrete		1.89	CU M
Footing Concrete		5.71	CU M
FTB Concrete		3.51	CU M
SOG Concrete		9.35	CU M
Column Concrete		12.02	CU M
Suspended Beam Concrete		6.08	CU M
S-1 Concrete		6.37	CU M
RB-1 Concrete		2.65	CU M
REBAR			
FOOTING			
16mm Dia. Footing Rebar		245.76	M
COLUMN			
16mm Column Rebar		526.88	M
12mm Column Rebar		317.6	M
10mm Column Rebar		1855.75	M
FTB-1			
16mm FTB-1 Rebar		313.1	M
10mm FTB-1 Rebar		448.14	M
SOG			
10mm SOG Rebar		525.12	M
SUSPENDE BEAMS			
16mm Suspended Beams		532.85	M
10mm Suspended Beams		773.68	M
SUSPENDE SLABS			
10mm S-1 Rebar		1281.43	M
ROOF BEAMS			
12mm RB-1 Main Rebar		238.76	M
10mm Roof Beam Rebar		393.96	M
FORMWORKS			
TOTAL HEIGHT		92	M
COLUMN FORMWORKS		110.4	SQ M
TOTAL LENGTH		87.28	M
SUSPENDE BEAM FORMWORKS		87.28	SQ M
SLAB FORMWORKS		64.23	SQ M
CEILING WORKS			
TOTAL PERIMETER		235.36	M
3.5mm THK Ficem Board		122.19	SQ M
PVC SPANDREL		41.01	SQ M
TILE WORKS			
0.3x0.3 Non-skid Ceramic Tiles		14.71	SQ M
0.3x0.3 Non-skid Textured Ceramic Tiles		2.52	SQ M
0.4x0.4 Ceramic Tiles		53.7	SQ M
0.4x0.4 Non-skid Ceramic Tiles		8.81	SQ M
0.6x0.6 Ceramic Tiles		50.66	SQ M
Plain Cement Groove Finish		41.63	SQ M
Solid Wood Plank		5.74	SQ M



SAMPLE BLUEBEAM REVU QUANTITY TAKEOFF

1 TILE WORKS



1 GROUND FLOOR PLAN
A-2 SCALE 1:75M

2 SECOND FLOOR PLAN
A-2 SCALE 1:75M

FLOOR FINISHES

Description	Quantity	Unit
0.3x0.3 Non-skid Ceramic Tiles	14.71	sq m
0.3x0.3 Non-skid Textured Ceramic Tiles	2.52	sq m
0.4x0.4 Ceramic Tiles	53.70	sq m
0.4x0.4 Non-skid Ceramic Tiles	8.81	sq m
0.6x0.6 Ceramic Tiles	50.66	sq m
Plain Cement Groove Finish	41.63	sq m
Solid Wood Plank	5.74	sq m

2 CEILING WORKS

CEILING FINISHES

Description	Label	Quantity	Unit	Length
C-1	3.5mm Ficemboard on Metal Furring	122.19	sq m	150.25
C-2	PVC SPANDREL	41.01	sq m	85.11

Note: Drawings and project information are presented for training and professional portfolio purposes. Actual project records and confidential information are not reproduced.

04 SAMPLE ESTIMATING PROJECTS

4. CONSTRUCTION OF 2 KM ROAD – BRGY. KALIKID SUR, CABANATUAN CITY, NUEVA ECIJA

Estimated Construction Cost: USD 207,351.00

Scope: Road Plan & Profile | Civil 3D | DUPA | BOQ/Program of Works | DPWH Standards.


SAMPLE PROGRAM OF WORKS | BOQ

DESCRIPTION OF WORK TO BE DONE	% of Total	EQUIPMENT		
		DESCRIPTION	NEEDED	AVAILABLE
FACILITIES FOR THE ENGINEER	0.47%	Motorized Road Grader	1	
OTHER GENERAL REQUIREMENTS	2.85%	Vibratory Roller	1	
EARTHWORKS	2.54%	Water Truck/Pump	1	
SUBBASE AND BASE COURSE	33.06%	One Bagger Mixer	1	
SURFACE COURSE	59.63%	Concrete Vibrator	1	
BRIDGE CONSTRUCTION	0.60%	Bar Cutter, Single Phase	1	
DRAINAGE AND SLOPE PROTECTION STRUCTURES	0.85%	Concrete Saw	1	
	100.00%			


Spec's Item No.	DESCRIPTION	Unit	Quantity	DIRECT COST	
				Unit Cost	Total Cost
PART A FACILITIES FOR THE ENGINEER					
A.1.1(8)	Provision of Field Office for the Engineer (Rental Basis)	mo.	3.00	17,325.00	51,975.00
PART B OTHER GENERAL REQUIREMENTS					
B.5	Project Billboard/ Signboard	ea	3.00	6,392.34	19,177.02
B.7(2)	Occupational Safety & Health Program	ls.	1.00	206,936.31	206,936.31
B.8(1)	Traffic Management	mo.	3.00	2,611.22	7,833.66
B.9	Mobilization/Demobilization	ls.	1.00	81,656.47	81,656.47
PART C EARTHWORKS					
101(4)a1	Removal of Actual Structures/Obstruction (610mm dia.)(RCPC)	l.m.	16.00	506.59	8,105.38
102(2)	Surplus Common Excavation	m³	150.20	188.79	28,356.26
103(1)a	Structure Excavation (Common Soil)	m³	22.40	309.62	6,935.49
104(1)a	Embankment From Roadway Excavation	m³	120.16	128.02	15,382.53
104(2)a	Embankment From Borrow, Common Soil	m³	179.31	685.83	122,976.18
105(1)a	Subgrade Preparation (Common Material)	m²	4,660.00	21.34	99,444.40
PART D SUBBASE AND BASE COURSE					
200(1)	Aggregate Subbase Course	m³	3,824.85	958.17	3,664,856.52
PART E SURFACE COURSE					
311(1)b1	Portland Cement Concrete Pavement (Unreinforced) (0.20m thick).	m²	5,000.00	1,322.04	6,610,208.86
PART F BRIDGE CONSTRUCTION					
404(1)a	Reinforcing Steel Bar, Grade 40 (Minor Structures)	kgs.	28.14	81.38	2,290.04
405(1)a3	Structural Concrete Class A (Minor Structures)	m³	8.06	8,001.18	64,489.55
PART G DRAINAGE AND SLOPE PROTECTION STRUCTURES					
500(1)b1	Pipe Culverts (610mm dia.), Class IV	l.m.	14.00	3,444.73	48,226.27
500(1)b3	Pipe Culverts (910mm dia.), Class IV	l.m.	7.00	6,586.31	46,104.18

BREAKDOWN OF ESTIMATED EXPENDITURES :		% of Total			
Labor :	Man-days :	P	1,235,679.44	11.04%	A. Direct Cost Sub-Total : P 11,084,954.12
Materials :	P	6,398,742.41	57.15%		B. Construction Eng'g. : 112,000.00
Rental of Equipment :	P	854,524.86	7.63%		C. Total & Miscellaneous :
Fuel, Oil, Spare Parts & Maintenance of Equipment :					D. Contingencies :
Others :	P	2,596,007.41	23.18%		E. Prelim. Engineering :
Overhead :	P	112,000.00	1.00%		F. Quality Control :
TOTAL :	P	11,196,954.12	100.00%		G. Project Supervision : P 11,196,954.12
					H. Total Estimated Cost : SAY P 11,200,000.00

1 Road Cross Section



2 Road Plan and Profile



Note: Drawings and project information are presented for training and professional portfolio purposes. Actual project records and confidential information are not reproduced.

05 CONSTRUCTION & QA/QC EXPERIENCE

1. 500 KV TRANSMISSION LINE GRID INTERCONNECTION – TERRA SOLAR PROJECT

PROJECT SCOPE: Earthworks • Site Layout & Survey • Tower Foundations • Reinforcement & Formwork • Concrete Works • Tower Erection • Material Inspection

ROLES AND RESPONSIBILITIES:

- Reviewed construction drawings, rebar details, **Bar Bending Schedules (BBS)**, rebar cutting lists, **BOQ**, and **BOM** to support construction accuracy and quantity requirements.
- Monitored tower foundation and erection activities, including **progress monitoring**, **site inspections**, inspection reports, and construction documentation.
- Conducted and documented **material inspections and testing** in accordance with applicable ACI and ASTM requirements, including concrete compressive strength and rebar tensile and bending tests.
- Prepared and monitored **RFIs**, **Inspection and Test Plan (ITP)**, **progress billing documents**, BOQ/BOM reports, **Job Order Requests (JOR)**, and **Matrix of Responsibility (MOR)** to support project implementation and documentation.
- Conducted material receiving inspections and supported warehouse management, material scheduling, and inventory documentation.
- Coordinated site activities and **technical meetings** with MTerra Solar Philippines, JACOBS, Energy China, Power China, subcontractors, and liaison personnel, supporting project progress and **ISO 9001-based QA/QC requirements**.

TRANSMISSION TOWER CONSTRUCTION METHODOLOGY

FOUNDATION WORKS

1

Site Preparation:

Site clearing, leveling, grading and survey works layout.

2

Excavation:

Excavate to the design depth and dimensions; ensure safe slopes/shoring.

3

Setting out and Alignment:

Set the foundation center and check position, level, and alignment.

4

Reinforcement & Anchor bolt Installation:

Install as per design and ACI Standard.

5

Formworks Installation:

Install formworks with proper support and bracing.

6

Concrete Pouring/Casting:

Pour concrete as per approved mix design and ensure proper consolidation.

7

Concrete Curing:

Allow concrete to set for at least 24 hrs. Cure the concrete for required period.

8

Backfilling:


Backfill with suitable material and compact properly.

9

Quality Control:

Inspect reinforcement, anchor bolts, formwork, dimensions, and concrete quality.

90 TOWERS



ERECTION WORKS

10

Materials & Equipment:

Prepare and inspect all tower components, lifting equipment and accessories.

11

Site Preparation:

Clear the site of any debris or obstacle provide sufficient working space and access route.

12

Tower Component Assembly:

Sort and Assemble tower members at laydown area as per drawings.

13

Lifting and Erection:

Lift and install tower section using appropriate cranes and lifting procedures.

14

Alignment and Positioning:

Inspect the tower verticality, ensure the alignment of members according to drawings.

15

Bolt Tightening:

Install and tighten bolts to the specified torque. Apply locknuts and lock washers.

16

Inspection:

Conduct thorough inspection of all members, connection and accessories.

17

Quality Control:

Ensure all works comply with drawings, specification and applicable standards.

Project Standards:

Foundation Works
ACI 318 | ACI PRC-315 | ASTM C143 |
ASTM C31 | ASTM C39 | ASTM C172

Erection Works
ASCE 10 | AISC 360 | ASTM A123 |
ASTM A394 | ASTM F3125 | IEC 60826

Note: Project information and documentation are presented for professional portfolio purposes. Actual project records and confidential company information are not reproduced.

05 CONSTRUCTION & QA/QC EXPERIENCE

2. MTERRA SOLAR PHASE 1 PHOTOVOLTAIC PROJECT – 1.4 GW SOLAR PV

PROJECT SCOPE: Site Clearing & Grading • Site Layout • Screw Pile Installation
Mounting Structures • PV Module Installation

ROLES AND RESPONSIBILITIES:

- Supervised **civil and structural construction activities**, conducted **quality trainings** on proper construction methodologies from screw pile installation to mounting structure and PV module installation, ensuring compliance with approved drawings and specifications.
- Conducted **QA/QC inspections** in accordance with **ISO 9001**, including construction activities inspections, material verification, testing, workmanship monitoring, and quality control.
- Prepared and managed **Work Inspection Request (WIR)**, **Quality Control Reports (QCRs)**, **Non-Conformance Reports (NCRs)**, inspection records, quality certifications, and other **QA/QC documentation** through project closeout.
- Monitored project **progress and scheduling**, coordinated site activities, and followed up on work targets and pending works.
- Coordinated with MTerra Solar Philippines, JACOBS, CEEC, subcontractors, and suppliers to facilitate inspections, resolve technical issues, and maintain project progress.

PHOTOVOLTAIC CONSTRUCTION METHODOLOGY

SCREW PILE INSTALLATION

1

Site Preparation:

Site clearing, leveling, grading and survey works layout.

2

Staked Point Layout:

Verify the location, spacing, and alignment of staked points against the approved plan before piling.

3

Ground Screw Piling:

Verify the location, elevation, and plumbness of screw piles based on approved plans.

4

Screw Pile Rectification:

Monitor the rectification of out of tolerance, refusal, and damage piles.

5

QA/QC Inspection:

Inspect materials, equipment, & installation, for compliance with the approved methodologies.

6

Material Inspection:

Organized and inspect materials for damage, defects, and completeness.

8

Subrail & Tension Rod Installation:

Installed subrails in the specified sequence and ensured proper installation of tension rods.

7

Main Rail & Strut Installation:

Installed posts and struts at each piles, connect struts at main rails, and verified proper bolt installation and torque.

9

QA/QC Inspection:

Inspection of structure in accordance to the plans and specification, verified bolt torque and member completeness.

10

Module Installation: Installed modules by verifying proper clamp connection, alignment, and positioning. Followed the specified installation sequence.

11

QA/QC Inspection: Verified module installation in accordance to plan. Inspect modules for construction related damage and ensured proper rectification.

PV MODULE INSTALLATION

Note: Project information and documentation are presented for professional portfolio purposes. Actual project records and confidential company information are not reproduced.

05 CONSTRUCTION & QA/QC EXPERIENCE

3. 35 KV OVERHEAD LINE TOWER – TERRA SOLAR POWER PLANT


PROJECT SCOPE: Earthworks • Site Layout Survey • Tower Substructure/Foundation • Tower Erection

ROLES AND RESPONSIBILITIES:

- Monitored tower construction progress and site activities, including earthworks, tower foundation, anchor bolt installation, concrete works, and tower erection.
- Prepared and scheduled **WIRs**, coordinated inspections, and monitored **QCR/NCR** status, **rectification works**, and close-out documentation.
- Prepared **Work Method Statements (WMS)** for earthworks, tower foundation, and tower erection, ensuring proper construction methodologies and QA/QC requirements.
- Conducted **site inspections** and **coordinated** with subcontractors and project stakeholders to address technical issues, implement rectifications, and maintain quality and construction progress.

TOWER PROGRESS MONITORING 80 TOWERS

LEGEND		
SYMBOL	STATUS	QTY.
○	With IFC Drawing	80
✗	Land Access Constraint	26
●	Ongoing Excavation	11
●	Completed Excavation	24
●	Poured Lean Concrete	14
●	Rebar Installation	7
●	Concreted Footing	6



TOWER FOUNDATION PROGRESS MAP
FOUNDATION CONSTRUCTION STATUS TRACKING

Illustrative representation of foundation work status monitoring.
Project-specific identifiers and information have been anonymized.

NOTE:


- This diagram is for portfolio presentation only.
- Project-specific tower IDs, locations, and details have been removed for confidentiality.
- Demonstrates QA/QC monitoring and progress tracking methodology.

4. MEDIUM VOLTAGE POWER STATION (MVPS) – TERRA SOLAR POWER PLANT, BLOCK D

PROJECT SCOPE: Earthworks • Site Layout Survey • Substructure • Superstructure

ROLES AND RESPONSIBILITIES:

- Inspected **concrete pouring** for substructure and superstructure works in accordance with **ACI 304R-00**, ensuring proper placement, consolidation, and curing.
- Performed and inspected **fresh concrete testing and sampling**, including Slump (**ASTM C143**), Temperature (**ASTM C1064**), Specimen Making & Curing (**ASTM C31**), and Compressive Strength (**ASTM C39**).
- Verified concrete quality and design mix in accordance with **ACI 211.1**, ensuring required strength, durability, and workability.



5. CONTROL BUILDING – TERRA SOLAR POWER PLANT, BLOCK D

PROJECT SCOPE: Earthworks • Site Layout Survey • Substructure

ROLES AND RESPONSIBILITIES:

- Performed **site layout** and **provided survey data** for foundation excavation, rebar, concrete layout, and elevations in accordance with approved design drawings.
- Inspected and monitored **foundation works**, including **Dynamic Cone Penetration Test (DCPT)** soil testing and bearing capacity verification, as well as **concrete and rebar testing** in accordance with applicable standards.
- Prepared and managed **WIRs, ITPs, rectification works, and site progress documentation**, ensuring QA/QC compliance and proper close-out.




06

CERTIFICATIONS & TRAINING

1. BLUEBEAM AND PLANSWIFT TRAINING AND WORK SHOP: DIGITAL QUANTITY TAKEOFF AND ESTIMATION FOR AEC PROFESSIONALS

XSTRUCTURES ENGINEERING CONSULTANTS
AUGUST 3 – 7, 2026

COURSE OUTLINE: User Interface | Plan Management | Plan Overlay & Comparison | Annotations & Scaling | Takeoff Tools | Organization & Visual Control | Cost Estimation | Template & Reporting Workflows | Software



2. MANUAL CONSTRUCTION BUILDING ESTIMATE: WITH AID OF MICROSOFT EXCEL AND AUTOCAD



MSTCONNECT | AUGUST 12 – 16, 2024

COURSE OUTLINE: Introduction to Estimate | Structural Estimate | Architectural Estimate | Sanitary & Electrical | Cost Estimate in Actual



3. QUALITY ASSURANCE & QUALITY CONTROL IN CONSTRUCTION

MSTCONNECT | JULY 11, 2025

COURSE OUTLINE: Fundamentals of QA/QC | Industry Standards & Code Compliance | QA/QC Planning | Site Deficiency Prevention | Documentation & Auditing | Quality Monitoring





06


CERTIFICATIONS & TRAINING

4. STRUCTURAL ANALYSIS & DESIGN — 3-STOREY COMMERCIAL BUILDING | NSCP 2015 & STAAD

PHILIPPINE INSTITUTE OF CIVIL ENGINEERS,
CENTRAL LUZON STATE UNIVERSITY
MAY 27, 2023



STAAD.Pro



5. CERTIFICATE OF COMPLETION | DPWH ENGINEERING APPRENTICESHIP



DPWH PLANNING & DESIGN SECTION
JUNE 14, 2022 TO JULY 23, 2022

SCOPE: Planning, Design & Estimating of
Horizontal and Vertical Structures

THANK YOU. LET'S CONNECT

AVAILABLE FOR: Remote / WFH,
Construction Estimating, Quantity Takeoff,
Quantity Surveying, Construction VA



ENGR. RON MAR B. PANGILINAN



EMAIL: Pangilinan.ronmarb@gmail.com



LinkedIn: linkedin.com/in/engr-ron-mar-pangilinan/
Portfolio: yourportfolio.com



CONTACT NO.:
+63960-244-6185 / +63967-084-0495



ADDRESS:
San Leonardo, Nueva Ecija, Philippines 3102

LINKEDIN

WEBSITE

GMAIL

